BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20408

SCHEDULE-B

NAME OF WORK: Filling of pot holes in main and cross roads of Bagalagunte Ward no.14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor G N RAMESH		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	457.27	77.34	Rupees Seventy Seven and Thirty Four Paise Only	35365.26
2	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Cum	383.06	1593.98	Rupees One Thousand Five Hundred Ninety Three and Ninety Eight Paise Only	610589.98
3	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications - Filling pot holes and patch repairs with bituminous concrete, 40mm	Sqm	1532.3	344.51	Rupees Three Hundred Forty Four and Fifty One Paise Only	527875.45
4	Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 4 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete	Cum	457.27	67.62	Rupees Sixty Seven and Sixty Two Paise Only	30920.60
					Total	1204751.29
					Percentage	-7.18%

Signature of the Contractor

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer